## **BUDGET PROPOSAL**

Jason Larson 801.478.8165

Project Name: Sommet Blanc Tower C Date: 11/23/2022

Project Location: 9300 Marsac Ave, Park City, UT, 84060 Proposal No.: 42824

Bid To: Interested Bidders

Attention: Estimating Team

Ce

Addenda: Spec. Sections: , None

Plans/Dates: (2022.10.10) [S...] Sheets listed on S0.01 (2022.10.03) [A...] Sheets, listed on A0.01.A.

These Drawings may represent an incomplete set of bid documents.

Upon receipt of a complete set, Steel Encounters reservs the right to reprice and reschedule.

### WE PROPOSE TO FURNISH: (FoB Job Site)

- 1. Steel Deck as specified on the Structural Plans.
  - a) 20 Gage 24"-N G60 Interlocking roof deck.
- 2. Deck Accessories.
  - a) none

Please Note: Steel Encounters is bidding deck and fastening per plans and specs.

Required side lap fastened is: button punch, seam welded, or screwed (as applicable). Please make your erector aware of this.

Two Hundred Eighty Three Thousand Nine Hundred Twenty Five Dollars and Forty Three Cents

Voluntary Adds:

Limited Period Use of proprietary deck seam tool (EOR to verify) ------\$800.00

## This proposal is subject to and conditional upon:

- 1. To process a purchase order we must have General Contractor name and address and job site address.
- 2. An order received by 2022.12.18. All materials must ship from plant no later than 2023.09.30 for deck. If material is shipped after these dates this proposal is subject to price escalations, surcharges, delays, or even availability issues. Note: This is not a delivery date it is only the date offered to us by our suppliers to avoid cost increases due to escalations. Contact our office for current fabrication and delivery schedules.
- 3. If we are to submit our invoices through Textura, contractor will be responsible for associated fees.
- 4. Any materials delivered to a location other than the jobsite will be accepted as being delivered to the jobsite and incorporated into the intended structure.

 Salt Lake Office
 525 East 300 South, Salt Lake City, UT 84102
 801.478.8100

 Seattle Office
 2300 W. Commodore Way, Ste. 200, Seattle, WA 98199
 206.281.8500

11/23/2022, 9:17 AM Page1 of 2

# **BUDGET PROPOSAL**

Jason Larson 801.478.8165

## SPECIFIC QUALIFICATIONS:

## Deck:

- 1. Bidding 20 gauge N roof deck. Per notes 20 gauge minimum. EOR is responsible to size the deck gauge.
- 2. Bidding interlocking side lap.

#### SPECIFIC EXCLUSIONS:

### Deck:

- 1. Short Cuts. Deck Lengths Less than 6'-0" require Field Cutting. By Others.
- 2. Any composite floor deck. None found on plans none considered.

#### **GENERAL QUALIFICATIONS:**

#### Project:

- 1. Material payment in full Net 30 days no discounts or retention. Because Steel Encounters is a material supplier only, we will only accept a Purchase Order or Steel Encounters Signed Proposal. We will not accept a subcontract agreement. The summary, terms and conditions of this proposal, are not subject to change or deviation by purchasers; nor do we assume any responsibility or liability under contracts, agreements, or covenants between the purchaser and others. Contractual agreements shall not contain a clause that makes payment by Owner a condition precedent to Buyers obligation to make payment to Steel Encounters. NO PENALTIES, EXTENDED GENERAL CONDITIONS COSTS, OR LIQUIDATED DAMAGES OF ANY KIND WILL BE ACCEPTED, unless approved by Steel Encounters, Inc.
- Back Charges: In the event of field repair work which may incur back-charge costs to Steel Encounters,
   Steel Encounters must be notified at the time the problem is detected and be given the opportunity to review, verify and rectify the problem.
   If not, Steel Encounters will not be held liable for those charges.
  - Said indemnification shall be limited to Steel Encounter's degree of fault in comparison to all others who may be at fault in whole or in part.
- 3. Steel Encounters reserves the right to pass on any sales tax rate adjustments which occur between the proposal date and the material delivery date.
- If Steel Encounters Line of Credit (LOC) is used to pay for materials or labor prior to receiving contract payment. Contract payments will be pledged as collateral to said LOC.
- 5. Steel Encounters is not an engineering firm. Steel Encounters will not generate any loads and is only responsible to include those loads clearly shown on the contract documents. The Engineer of Record (EOR) is responsible to provide Steel Encounters with all design criteria.

  Steel Encounters is only responsible to provide its joists and/or deck products per the design parameters provided by the EOR.
- 6. It shall be the Contractor's responsibility to receive and unload materials at the jobsite, to check for damage, and to verify that quantities delivered agree with carrier's bills and/or manufacturer's packing lists.
- 7. All material is furnished in accordance with (SDI) Steel Deck Institute specifications.
- 8. Submittal and field use drawings will NOT be stamped by an engineer per IBC #2207
- 9. Proposal does NOT include any Domestic or Recycled content requirement. ( unless noted otherwise )
- 10. Due to the difficulty in obtaining field measurements in a timely manor, all deck at infills and minor openings will be supplied long for field cutting.

## **GENERAL EXCLUSIONS:**

## Project:

- 1. BIM
- 2. Any items appearing on sheets other than Architectural or Structural sheets. (unless noted otherwise)
- 3. Structural or miscellaneous steel.
- 4. Touch up or galvanizing repair paint.
- 5. Field measuring.
- 6. Accommodating fire code requirements. Steel Encounters assumes materials have been selected by A/E to satisfy such requirements.
- 7. All skews, curves, bevels, notches and holes. ( to be field cut by others ). Note: Deck ends are square and cut to length.
- 8. Deck sidelap punching tool. (Button Punch)
- 9. Venting of deck. (unless noted otherwise)
- 10. Deck at canopies or stair landings unless gauge and type is specified on the drawings.
- 11. Cleaning of deck or preparation prior to field painting.
- 12. Painting of Deck.
- 13. Galvanized deck is supplied passivated and may require cleaning prior to field painting. (materials and labor by others)
- 14. Deck fasteners, unless otherwise noted.

Jason Larson	_
STEEL ENCOUNTERS	_
Accepted By	Date

11/23/2022, 9:17 AM Page2 of 2