



Olson Kundig

subject



Page 10 of 10



A. DRAWINGS ARE TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE DIAGNOSTIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATIONS EXCEPT WHERE DIMENSIONS ARE SHOWN. ELECTRICAL WORK IS SHOWN ON THE STANDARD ELECTRICAL SYMBOLS AND CONVENTIONS. CONTRACTOR SHALL DOING WORK. VERIFY MEASUREMENTS PERTAINING THERE TO AND ASSUME RESPONSIBILITY THEREFOR. ANY SUBSTANTIAL DIFFERENCES BETWEEN DRAWINGS AND CONDITIONS IN THE FIELD SHALL BE SUBMITTED TO THE ARCHITECT FOR REVIEW AND APPROVAL BEFORE PROCEEDING WITH WORK.

B. WORKER FORNISHED INCLUDES ALL MATERIALS AND EQUIPMENT REQUIRED TO INSTALL COMPLETE ELECTRICAL SYSTEM AS INDICATED ON THESE DRAWINGS AND AS SPECIFIC REFER TO ELECTRICAL CONNECTION SCHEDULE FOR CONDUIT, WIRING, COPD, DOWEL, AND EQUIPMENT.

C. VERIFY ELECTRICAL CODES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.

D. VERIFY ELECTRICAL CONDITIONS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH OTHER TRADES AND USE CHASES AND CEILING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO INSTALLATION.

E. REFER TO MECHANICAL AND PLUMBING PLANS FOR EXACT LOCATION OF HVAC/PLUMBING EQUIPMENT.

F. CONDUIT, WIRE AND J-BOXES FOR ROUTING SHOWN. QUANTITY AND SIZES OF J-BOXES TO BE DETERMINED BY CONTRACTOR.

G. CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OF ANY ELECTRICAL CIRCUITS OR STRUCTURES DAMAGED BY WORK. THERE WILL BE REPAIR IMMEDIATELY. THERE WILL BE NO DISRUPTION OF SERVICE OUTSIDE OF CONSTRUCTION ZONE/AREA. PROVIDE TAMPER PROOF RECEPTACLES IN RESIDENTIAL UNITS AND ALL COMMON AREAS.

1. ELECTRICAL CONTRACTOR TO SUPPLY AND INSTALL A DIRECT CONNECTION, WIRING AND RIGID CONDUIT FROM CEILING MOUNTED JUNCTION BOX NOTED TO THE FLOOR MOUNTED NEXGEN CONTROLLER. EXACT LOCATION OF THE NEXGEN CONTROLLER IS TO BE COORDINATED ON SITE PRIOR TO CONSTRUCTION.
2. DUPLEX RECEPTACLE TO BE INSTALLED IN THE ELEVATOR PIT. COORDINATE EXACT LOCATION WITH ELEVATOR CONTRACTOR.
3. COORDINATE EQUIPMENT LAYOUT WITH ELEVATOR PROVIDER PRIOR TO ROUGH IN. PROVIDE ALL CODE-REQUIRED CLEARANCES.
4. EQUIPMENT RECEPTACLE
5. ELECTRICAL SUBPANEL WITH ISOLATED GROUND IS DEDICATED FOR BOWLING EQUIPMENT. GENERAL LIGHTING AND RECEPTACLE LOADS SHALL NOT BE CONNECTED TO THIS PANEL.
6. PROVIDE GFI PROTECTION ON ALL ELECTRICAL PANELS. GFI PROTECTION MAY BE INTEGRAL TO CIRCUIT BREAKER, OR MAY BE MODULE MOUNTED ADJACENT TO PIT RECEPTACLE.
7. PROVIDE CONNECTION FOR MECHANICAL PRESSURE CONTROLLER WITH 120V/1PH/1WHP ELECTRICAL POWER.
8. PROVIDE CONNECTION FOR MECHANICAL ENERXER SMD-S8 CONTROLLING DAMPER OFF BOLLER EXHAUST STACK WITH 120V/1PH/1WHP ELECTRICAL POWER.

