



Olson Kundig

---



E2.2B.03



- A. DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE NOT DIMAGRAMMATIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATIONS EXCEPT WHERE DIMENSIONS ARE SHOWN. ELECTRICAL WORK IS SHOWN ON STANDARD 1/4" = 1' SCALE UNLESS OTHERWISE NOTED. CONTRACTOR SHALL BE RESPONSIBLE FOR WORK. VERIFY MEASUREMENTS PERTAINING THEREIN AND ASSUME RESPONSIBILITY THEREOF. ANY SUBSTANTIAL DIFFERENCES BETWEEN DRAWINGS AND CONDITIONS IN THE FIELD SHALL BE SUBMITTED TO THE ARCHITECT FOR CONSTRUCTION MANAGEMENT FOR CONSIDERATION BEFORE PROCEEDING WITH WORK.
- B. WORK PERFORMED INCLUDES LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO INSTALL AND TEST ALL ELECTRICAL SYSTEMS AND EQUIPMENT SHOWN ON THE DRAWINGS. CONTRACTOR SHALL REFER TO ELECTRICAL CONNECTION SCHEDULE FOR CONDUIT, WIRING, COPD, DEVICES, AND EQUIPMENT.
- C. REFER TO MECHANICAL DRAWINGS FOR VENTILATION, HEATING, AND COOLING REQUIREMENTS. VERIFY EQUIPMENT TYPES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.
- D. ELECTRICAL CONDUITS IN FINISHED SPACES SHALL BE CONCEALED COORDINATE WITH OTHER TRADES AND USE CHASES AND CEILING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO POURING CONCRETE.
- E. REFER TO MECHANICAL AND PLUMBING PLANS FOR EXACT LOCATION OF HVAC/PLUMBING EQUIPMENT.
- F. CONDUIT, WIRE, AND J-BOXES FOR CIRCUITING SHOWN. QUANTITY AND SIZES OF J-BOXES TO BE DETERMINED BY CONTRACTOR.
- G. CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OF ANY ELECTRICAL CIRCUITS DAMAGED BY CONSTRUCTION. REPAIRS WILL BE REPAIRED IMMEDIATELY. THERE WILL BE NO DISRUPTION OF SERVICE OUTSIDE OF CONSTRUCTION ZONE AREA.
- H. PROVIDE PROOF PROTECTIVE RECEPTACLES IN RESIDENTIAL UNITS AND ALL COMMON AREAS AS PER NEC 408.12.

- 1 DUPLEX RECEPTACLE TO BE INSTALLED IN THE ELEVATOR PIT. COORDINATE EXACT LOCATION WITH ELEVATOR CONTRACTOR.
- 2 COORDINATE EQUIPMENT LAYOUT WITH ELEVATOR PROVIDER PRIOR TO ROUGH IN. PROVIDE ALL CODES REQUIRED & CLEARANCES ABOVE EQUIPMENT.
- 3 COMMUNICATIONS RACK IS TO BE SUPPLIED BY OTHERS AND INSTALLED BY ELECTRICAL CONTRACTORS AS PART OF THIS SCOPE OF WORK.
- 4 FLOOR UNIT DESIGNED TO BE PART OF A SPLIT SYSTEM AND IS TO BE POWERED BY THE OUTDOOR UNIT ELECTRICAL CONTROLLER. IT IS TO SUPPLY AND INSTALL THE WIRING AND CONDUITS BETWEEN THE OUTDOOR UNIT AND THE INDOOR UNIT AS PART OF THIS SCOPE OF WORK. REFER TO THE EQUIPMENT CONNECTION SCHEDULE FOR ADDITIONAL INFORMATION.
- 5 PROVIDE CONDUIT, BOXES, AND WIRING AS REQUIRED BY MANUFACTURER FOR DOOR CONTROLS.
- 6 PROVIDE CONNECTION FOR MOULATING PRESSURE CONTROLLER WITH 120V/1PH ELECTRICAL POWER.
- 7 PROVIDE CONNECTION FOR MECHANICAL EXHAUST, SMD8-8 MOULATING DRAFTER OFF FLOOR EXHAUST WITH 120V/1PH ELECTRICAL POWER.

