


Olson Kundig

project: **SOMMET BLANC**
3300 Marsac Ave (B2 East Parcel)



no.	date	t
-----	------	---

IFC Set 3 of
5/31/2024

TOWER A/B ELECTRICAL
LIGHTING PLAN - UNIT K

E3.4.K

A. DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE DIAGNOSTIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATION OR HEIGHT OF UTILITIES. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTHS OF UTILITIES USING STANDARD UTILITY SYMBOLS. BEFORE ORDERING MATERIALS OR COMMENCEMENT WITH WORK, VERIFY MEASUREMENTS PERTAINING THEREOF AND CORRECT ANY DISCREPANCIES. THE CONTRACTOR SHALL SUBMIT ALL FIELD DRAWINGS AND CONDITIONS IN THE FIELD SHALL BE SUBMITTED TO THE CONSTRUCTION MANAGER FOR CONSIDERATION BEFORE PROCEEDING WITH WORK.
 B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS TO INSTALL A COMPLETE ELECTRICAL SYSTEM AS INDICATED ON DRAWINGS AND SPECIFICATIONS.
 C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS FOR EMERGENCY TO EMERGENCY POWER SOURCE AS INDICATED ON DRAWINGS.
 D. REFER TO LUMINAIRE SCHEDULE FOR INFORMATION.
 E. FOR ALL LUMINAIRE, THE CONTRACTOR SHALL IDENTIFY MANUFACTURER, VERIFY REFERENCE CATALOG NUMBERS FOR ACCURACY.
 F. VERIFY EQUIPMENT SIZES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.
 G. ELECTRICAL CONDUITS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH MECHANICAL AND USE CONCEALED CONDUIT WHEN AVAILABLE.
 H. ALL ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO POUR-IN.
 I. CONTRACTOR REMOVE DOWEL MOUNTING LOCATIONS WITH ARCHITECT PRIOR TO POUR-IN.
 J. COORDINATE LUMINAIRE VOLTAGE WITH ARCHITECT AND OWNER PRIOR TO PURCHASE AND INSTALLATION TYPE FOR ALL LIGHTING.

- 1 LITRON WIRELESS PRO CONTROL SWITCH IS TO BE SUPPLIED AND INSTALLED FOR SHADE CONTROL.
- 2 LIGHT FIXTURE LOCATED IN CLOSET IS TO BE CONTROLLED BY CONTROL DOOR JAMB SWITCH.
- 3 SUPPLY AND INSTALL LITRON RADIO RAS SYSTEM TO PROVIDE PARTIAL LIGHTING CONTROL IN THE RESIDENTIAL UNITS MASTER BEDROOM (DENOTED AS B2) AND ALL ROOMS WITH MORE THAN THREE (3) LIGHTING CONTROL ZONES ARE TO BE CONTROLLED BY THE LITRON RADIO RAS SYSTEM. ALL ROOMS WITH THREE (3) LIGHTING CONTROL ZONES OR LESS ARE TO BE CONTROLLED BY LOCAL SWITCHES.
- 4 SUPPLY AND INSTALL CEILING MOUNTED JUNCTION BOX COMPLETE WITH CAPPED LIGHTING CIRCUIT WIRING FOR INSTALLATION OF FUTURE CEILING LIGHT FIXTURE.
- 5 REFER TO ARCHITECTURAL DRAWINGS AND ELEVATIONS FOR EXACT DIMENSIONS AND MOUNTING LOCATION OF LIGHT FIXTURE. SEE LSC COORDINATION WITH ALL OTHER CONTRACTORS PRIOR TO INSTALLATION.

