


Olson Kundig

project:  
**SOMMET BLANC**  
3200 Morris Ave. (B3 East Branch)



no.	date	by
-----	------	----

### E3.4.O

A. DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXACT LOCATIONS OF DEVICES AND ARE DIAGRAMMATIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATIONS EXCEPT WHERE DIMENSIONS ARE SHOWN. ELECTRICAL WORK IS SHOWN ON PLANS USING THE CONVENTIONAL SYMBOLS AND NOTATION OF THE NATIONAL ELECTRICAL CODE. THE CONTRACTOR SHALL VERIFY MEASUREMENTS PERTAINING THERETO AND ASSUME RESPONSIBILITY THEREFOR. ANY SUBSTANTIAL DIFFERENCES BETWEEN DRAWINGS AND CONDITIONS IN THE FIELD SHALL BE SUBMITTED TO THE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO PROCEEDING WITH WORK.

B. THE CONTRACTOR SHALL FURNISH LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO INSTALL A COMPLETE ELECTRICAL SYSTEM AS INDICATED ON DRAWINGS AND SPECIFICATIONS. PROVIDE EXT GROUND SIGNALS AND CONNECT EXT SIGNALS AND LUMINAIRES NOTED AS EMERGENCY TO THE EMERGENCY POWER SOURCE SYSTEM.

C. REFER TO LUMINAIRE SCHEDULE FOR INFORMATION.


D. FIXTURE CATALOG NUMBERS ARE SUBJECT TO CHANGE BY MANUFACTURER. VERIFY FIXTURE CATALOG NUMBERS FOR THE EQUIPMENT TO BE USED.

E. VERIFY EQUIPMENT SIZES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.

F. ELECTRICAL CONDITIONS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH OTHER TRADES AND USE CASES AND CEILING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO ROUGH-IN.

G. COORDINATE REWIRE DRYER MOUNTING LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN. PROVIDE LUMINAIRE, EQUIPMENT, AND MATERIALS TO THE OWNER PRIOR TO PURCHASE AND INSTALLATION TRYOUT FOR ALL UNIT LIGHTING.

- 1 LUTRON WIRELESS PICO CONTROL SWITCH IS TO BE SUPPLIED AND INSTALLED FOR SHADE CONTROL.
- 2 LIGHT FIXTURE LOCATED IN CLOSETS ARE TO BE CONTROLLED BY CLOSET DOOR JAM SWITCH.
- 3 REFER TO ARCHITECTURAL DRAWINGS AND ELEVATIONS FOR EXACT DIMENSION AND MOUNTING LOCATION OF
- 4 LIGHT FIXTURE TYPE LU4. COORDINATE WITH MILLWORK CONTRACTOR PRIOR TO INSTALLATION.
- 5 SUPPLY AND INSTALL CEILING MOUNTED JUNCTION BOX COMPLETE WITH CAFFEED LIGHTING CIRCUIT WIRING
- 6 INSTALLATION OF FUTURE LIGHT FIXTURES.
- 7 SUPPLY AND INSTALL LUTRON RADIO RAS2 SYSTEM TO PROVIDE PARTIAL LIGHTING CONTROL IN THE
- 8 RESIDENTIAL UNITS MASTER BEDROOM (DENOTED AS BED 1) AND ALL ROOMS WITH MORE THAN THREE (3)
- 9 LIGHTING CONTROL ZONES. PROVIDE PARTIAL LIGHTING CONTROL IN THE LIVING ROOMS WITH
- 10 THREE (3) LIGHTING CONTROL ZONES OR LESS ARE TO BE CONTROLLED BY LOCAL DIMMERS.



1 TOWER C - ELECTRICAL LIGHTING UNIT PLAN - O  
SCALE: 1/4" = 1'-0"