SWITCHBOAR... MS-P2A1

Location: MAIN ELEC SWITCHBOARD 403SF
Main Bus: 4000 A
MCB: 4000A
Voltage: 480/277 Wye
AIC Rating: 65,000 A

Fed From: 277/480V OUTDOOR UTILITY XFMR
Wires: 4
Enclosure: 1
Bus Type: COPPER
Mounting: FLOOR

Neutual: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral NO

CKT	Circuit Description	# of Poles	Frame	Rating	Load	Remarks
1	LPH-BA1	3	400 A	400 A	250689 VA	
2	LPH-P2A1	3	400 A	400 A	57877 VA	
3	MPH-P2A1	3	400 A	400 A	255675 VA	
4	MPH-P1B1	3	800 A	800 A	493631 VA	
5	LPH-BB1	3	400 A	400 A	14354 VA	
6	T-EV-A	3	400 A	400 A	211200 VA	
7	SPARE	3	400 A	400 A	0 VA	
8	LPH-P2A2	3	400 A	400 A	21101 VA	
9	ELEVATOR S1	3	400 A	20 A	500 VA	
10	O-ATS-P2A	3	400 A	20 A	51700 VA	
11	S-ATS-P2A	3	400 A	400 A	263678 VA	
12	E-ATS-P2A	3	400 A	400 A	91277 VA	
13	LPH-P2B1	3	400 A	400 A	127179 VA	
14	ELEVATOR P3	3	400 A	400 A	500 VA	
15	SPARE	3	200 A	200 A	0 VA	
16	SPARE	3	200 A	200 A	0 VA	
17	SPARE	3	100 A	100 A	0 VA	
18	SPARE	3	100 A	100 A	0 VA	
				Total Conn. Load:		
				Total Amps:		

MS-P2A1 LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
Other	3560 VA		3560 VA		
RCPTS	117120 VA		63560 VA	**Total Conn. Load:**	1839360 VA
LTS	53153 VA		66441 VA	**Total Est. Demand:**	1796599 VA
MTRS	1358764 VA		1358764 VA	**Total Conn.:**	2212 A
HEAT	44064 VA		44064 VA	**Total Est. Demand:**	2161 A
MISC	240950 VA		240950 VA		
Power	5306 VA		5306 VA		
Lighting	3 VA		4 VA		
RCPT	14980 VA		12490 VA		

Notes:
*See Demand Factor Table

DEMAND FACTOR TABLE

LOAD TYPES	FACTORS										NEC REFERENCE
LTS	1.25										220.42
RCPTS	0-10kVA	>10kVA									
	1.00	0.50									220.44
MTRS	MAX	ALL OTHERS									
	1.25	1.00									220.50
ELEV	1	2	3	4	5	6	7	8	9	10 or more	
	1.00	0.95	0.9	0.85	0.82	0.79	0.77	0.75	0.73	0.72	620.14
KTCH	1	2	3	4	5	6 or more					
	1.00	1.00	0.90	0.80	0.70	0.65					220.56
HEAT	1.00										220.51
MISC	1.00										210.19
EXISTING	1.25										
RVN	1.25	LOAD INDICATED IS DEMAND LOAD FROM EQL. FEEDERS TO EQUIPMENT SIZED FOR CONNECTED LOAD									

BRANCH PANEL: LP-BA2

Location: TOWER A LEVEL B BOILER RM...
Main Bus: 100 A
MCB: 100A
Voltage: 120/208 Wye
AIC Rating: 10 kA

Fed From: LP-BA1
Wires: 4W + G
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: WALL MOUNTED

Neutral Bus: YES
Ground Bus: YES
Isolated Ground Bus: YES
200% Neutral: NO
Feed Through Lugs: NO

CKT	Circuit Description	Load Classification	Trip	Poles	A		B		C		Poles	Trip	Load Classification	Circuit Description	CKT
1	NEXGEN CONTROLLER J BOX	MISC	20 A	3	167 VA	580 VA					1	20 A	MISC...	BOWLING - FLOOR BOX	2
3	--	--	--	--			167 VA	180 VA			1	20 A	RCPTS	BOWLING - LANE FLOOR BOX	4
5	--	--	--	--					167 VA	0 VA	1	20 A	--	SPARE	6
7	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	8
9	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	10
11	SPARE		20 A	1					0 VA	400 VA	1	15 A	MISC	BOWLING - FOUL -LIGHTS	12
13	PERIPHERAL CONTROLLER...	RCPT	15 A	1	540 VA	0 VA					1	20 A	--	SPARE	14
15	PROTECTION SCREEN RCPT	RCPT	15 A	1			540 VA	1400...			1	20 A	MISC	BOWLING BALL LIFT	16
17	SPARE	--	20 A	1					0 VA	1400...	1	20 A	MISC	BOWLING OH MONITOR	18
19	SPARE	--	20 A	1	0 VA	720 VA					1	15 A	MISC	BOWLING - BUMPERS	20
21	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	22
23	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	24
25	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	26
27	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	28
29	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	30
31	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	32
33	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	34
35	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	36
37	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	38
39	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	40
41	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	42
			Total Load:		2407 VA		2287 VA		1967 VA						
			Total Amps:		20 A		19 A		16 A						

LP-BA2 LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
RCPTS	180 VA		180 VA		
MISC	5220 VA		5220 VA	**Total Conn. Load:**	6660 VA
RCPT	1260 VA		1260 VA	**Total Est. Demand:**	6660 VA
				Total Conn.:	18 A
				Total Est. Demand:	18 A

Notes:
*See Demand Factor Table

SWITCHBOAR... E-DSH-P2A

Location: MECH P255
Main Bus: 800 A
MCB: 800A
Voltage: 480/277 Wye
AIC Rating: 10 kA

Fed From: GENERATOR
Wires: 4
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: SURFACE

Neutual: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral NO

CKT	Circuit Description	# of Poles	Frame	Rating	Load	Remarks
1	E-ATS-P1C	3	200 A	200 A	0 VA	
2	S-ATS-P1C	3	300 A	300 A	0 VA	
3	O-ATS-P1C	3	200 A	200 A	0 VA	
4	E-ATS-P2A	3	400 A	400 A	91277 VA	
5	S-ATS-P2A	3	600 A	600 A	263678 VA	
6	O-ATS-P2A	3	400 A	400 A	51700 VA	
7	SPD	2	60 A	60 A	0 VA	
8	SPARE	3	200 A	200 A	0 VA	
9	SPARE	3	200 A	200 A	0 VA	
10	SPARE	3	200 A	200 A	0 VA	
11	SPARE	3	200 A	200 A	0 VA	
12	SPARE	3	100 A	100 A	0 VA	
13	SPARE	3	100 A	100 A	0 VA	
14	SPARE	3	100 A	100 A	0 VA	
15	SPARE	3	100 A	100 A	0 VA	
16	SPARE	3	60 A	60 A	0 VA	
17	SPARE	3	60 A	60 A	0 VA	
18	SPARE	3	60 A	60 A	0 VA	
				Total Conn. Load:		
				Total Amps:		

E-DSH-P2A LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
Other	289 VA		289 VA		
RCPTS	54860 VA		32430 VA	**Total Conn. Load:**	406655 VA
LTS	28207 VA		35259 VA	**Total Est. Demand:**	391278 VA
MTRS	304646 VA		304646 VA	**Total Conn.:**	489 A
MISC	18110 VA		18110 VA	**Total Est. Demand:**	471 A
Lighting	3 VA		4 VA		
RCPT	540 VA		540 VA		

Notes:
*See Demand Factor Table

SWITCHBOAR... S-DPH-P2A

Location: ELEC EMERGENCY SWITCHBOAR...
Main Bus: 600 A
MCB: 600A
Voltage: 480/277 Wye
AIC Rating: 22 kA

Fed From: S-ATS-P2A
Wires: 4
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: SURFACE

Neutual: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral NO

CKT	Circuit Description	# of Poles	Frame	Rating	Load	Remarks
1	SMPH-P2A1	3	225 A	225 A	23220 VA	
2	SMPH-P1B1	3	225 A	225 A	72458 VA	
3	ELEVATOR T1	3	60 A	60 A	42000 VA	
4	ELEVATOR T2	3	60 A	60 A	42000 VA	
5	ELEVATOR T3	3	60 A	60 A	42000 VA	
6	ELEVATOR T4	3	60 A	60 A	42000 VA	
7	SPD	2	60 A	60 A	0 VA	
8	SPARE	1	60 A	60 A	0 VA	
9	SPARE	3	100 A	100 A	0 VA	
10	SPARE	3	100 A	100 A	0 VA	
11	SPARE	3	100 A	100 A	0 VA	
12	SPARE	3	100 A	100 A	0 VA	
13	SPARE	3	60 A	60 A	0 VA	
14	SPARE	3	60 A	60 A	0 VA	
15	SPARE	3	60 A	60 A	0 VA	
16	SPARE	1	20 A	20 A	0 VA	
17	SPARE	1	20 A	20 A	0 VA	
18	SPARE	1	20 A	20 A	0 VA	
				Total Conn. Load:		
				Total Amps:		

S-DPH-P2A LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
MTRS	263678 VA		263678 VA		
MISC	0 VA		0 VA	**Total Conn. Load:**	263678 VA
				Total Est. Demand:	263678 VA
				Total Conn.:	317 A
				Total Est. Demand:	317 A

Notes:
*See Demand Factor Table

BRANCH PANEL: LPH-BA1

Location: TOWER A LEVEL B BOILER RM...
Main Bus: 400 A
MCB: 400A
Voltage: 480/277 Wye
AIC Rating: 35 kA

Fed From: MS-P2A1
Wires: 4W+G
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: WALL MOUNTED

Neutral Bus: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral: NO
Feed Through Lugs: NO

CKT	Circuit Description	Load Classification	Trip	Poles	A		B		C		Poles	Trip	Load Classification	Circuit Description	CKT
1	AHU - A-B1-1	MTRS	20 A	3	2720...	5820...					3	25 A	MTRS	SHWP A-B-2	2
3	--	--	--	--			2720...	5820...			--	--	--	--	4
5	--	--	--	--					2720...	5820...	--	--	--	--	6
7	BP - A-B-3	MTRS	15 A	3	1330...	5820...					3	25 A	MTRS	SHWP A-B-1	8
9	--	--	--	--			1330...	5820...			--	--	--	--	10
11	--	--	--	--					1330...	5820...	--	--	--	--	12
13	BP - A-B-2	MTRS	15 A	3	1330...	3880...					3	20 A	MTRS	PHWP A-B-2	14
15	--	--	--	--			1330...	3880...			--	--	--	--	16
17	--	--	--	--					1330...	3880...	--	--	--	--	18
19	BP- A-B-1	MTRS	15 A	3	1330...	3880...					3	20 A	MTRS	PHWP A-B-1	20
21	--	--	--	--			1330...	3880...			--	--	--	--	22
23	--	--	--	--					1330...	3880...	--	--	--	--	24
25	SCHWP A-B-2	MTRS	30 A	3	7483...	3880...					3	20 A	MTRS	PCHWP A-B-2	26
27	--	--	--	--			7483...	3880...			--	--	--	--	28
29	--	--	--	--					7483...	3880...	--	--	--	--	30
31	SCHWP A-B-1	MTRS	30 A	3	7483...	3880...					3	20 A	MTRS	PCHWP A-B-1	32
33	--	--	--	--			7483...	3880...			--	--	--	--	34
35	--	--	--	--					7483...	3880...	--	--	--	--	36
37	EF-A-B-1	MTRS	20 A	1	610 VA	1220...					1	20 A	MTRS	FPT A-B1-4 & FPT A-B1-5	38
39	LTS LEVEL B1	LTS	20 A	1			1793...	1000...			1	20 A	MTRS	FPT A-B1-1	40
41	LTS LEVEL B1	LTS	20 A	1					2410...	1360...	1	20 A	MTRS	FPT A-B1-3	42
43	EF-A-B-2	MTRS	20 A	1	803 VA	803 VA					1	20 A	MTRS	EF- A-B-2	44
45	BEF-A-1	MTRS	20 A	3			582 VA	1330...			3	20 A	MTRS	BEF-A-2	46
47	--	--	--	--					582 VA	1330...	--	--	--	--	48
49	--	--	--	--	582 VA	1330...					--	--	--	--	50
51	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	52
53	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	54
55	TRANSFORMER T-BA1-L...	Power...	110 A	3	2496...	7650...					3	40 A	MTRS	AHU-A-B1-2	56
57	--	--	--	--			1930...	7650...			--	--	--	--	58
59	--	--	--	--					2122...	7650...	--	--	--	--	60
			Total Load:		86800 VA		80494 VA		83395 VA						
			Total Amps:		315 A		291 A		303 A						

LPH-BA1 LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
	2300 VA		2300 VA		
LTS	4203 VA		5253 VA	**Total Conn. Load:**	250689 VA
MTRS	220807 VA		220807 VA	**Total Est. Demand:**	249710 VA
MISC	8240 VA		8240 VA	**Total Conn.:**	302 A
Power	360 VA		360 VA	**Total Est. Demand:**	300 A
RCPT	14060 VA		12030 VA		

Notes:
*See Demand Factor Table

BRANCH PANEL: LP-BA1

Location: TOWER A LEVEL B BOILER RM...
Main Bus: 250 A
MCB: 250A
Voltage: 120/208 Wye
AIC Rating: 10 kA

Fed From: T-BA1-L
Wires: 4W+G
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: WALL MOUNTED

Neutral Bus: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral: NO
Feed Through Lugs: NO

CKT	Circuit Description	Load Classification	Trip	Poles	A		B		C		Poles	Trip	Load Classification	Circuit Description	CKT
1	TOILET RCPTS	RCPT	20 A	1	720 VA	1728...					1	30 A	MTRS	GPS A-B-1	2
3	TOILET RCPTS	RCPT	20 A	1			720 VA	540 VA			1	20 A	RCPTS	BOWLING LOUNGE A002 BAR	4
5	RCPTS EMPLOYEE BREAK 008	RCPT	20 A	1					360 VA	360 VA	1	20 A	RCPT	BOWLING LOUNGE A002...	6
7	UH-A	MTRS	20 A	1	120 VA	180 VA					1	20 A	RCPT	MAIN SHOP RCPT	8
9	BOWLING RCPT	RCPT	20 A	1			1260...	180 VA			1	20 A	RCPT	MAIN SHOP RCPT	10
11	MECH CONTROLLER	MISC	20 A	1					1920...	720 VA	1	20 A	RCPT	RCPTS	12
13	MTRS BOILER ROOM 012	MTRS	20 A	2	5050...	900 VA					1	20 A	RCPT	HOUSEKEEPING RCPT	14
15	--	--	--	--			5050...	540 VA			1	20 A	RCPT	GAME LOUNGE RCPT	16
17	MTRS BOILER ROOM 012	MTRS	20 A	2					5050...	432 VA	1	20 A	MTRS	UH-A	18
19	--	--	--	--	5050...	1000...					1	15 A	RCPT	ARCADE RCPTS	20
21	B A-P2-1	MTRS	15 A	1			840 VA	1000...			1	15 A	RCPT	ARCADE RCPTS	22
23	B A-P2-2 & A-P2-3	MTRS	15 A	1					1680...	1500...	1	15 A	RCPT	ARCADE RCPTS	24
25	LP-BA2	Spare;...	100 A	3	2407...	1500...					1	15 A	RCPT	ARCADE RCPTS	26
27	--	--	--	--			2287...	1000...			1	15 A	RCPT	ARCADE RCPTS	28
29	--	--	--	--					1967...	432 VA	1	20 A	MTRS	UH-A	30
31	Power	Power	20 A	2	180 VA	500 VA					1	20 A	RCPT	RCPTS	32
33	--	--	--	--			180 VA	180 VA			1	20 A	RCPTS	RCPTS	34
35	MECH DAMPER	MTRS	20 A	1					960 VA	180 VA	1	20 A	RCPTS	RCPTS	36
37	RCPTS	RCPTS	20 A	2	180 VA	1920...					1	20 A	MTRS	MECH DAMPER	38
39	--	--	--	--			0 VA	360 VA			1	20 A	RCPTS;...	RCPT STAIR 02A A031/P270/...	40
41	AV RACK	Receptacle	20 A	2					180 VA	180 VA	2	20 A	RCPTS	RCPTS	42
43	--	--	--	--	180 VA	0 VA					--	--	--	--	44
45	AV RACK	Receptacle	20 A	2			180 VA	1375...			2	20 A	MTRS	SEP-4	46
47	--	--	--	--					180 VA	1375...	--	--	--	--	48
49	ELEV S1 SEISMIC SENSOR...	MISC	20 A	1	600 VA	1375...					2	20 A	MTRS	SEP-3	50
51	ELEV S1 CTRL ROOM GFI...	RCPTS	20 A	1			500 VA	1375...			--	--	--	--	52
53	ELEV S1 CAR LIGHT	MISC	15 A	1					500 VA	1375...	2	20 A	MTRS	SEP-2	54
55	ELEV S1 INTERCOM	MISC	15 A	1	0 VA	1375...					--	--	--	--	56
57	ELEV PIT GFI RCPT	RCPTS;...	20 A	1			360 VA	1375...			2	20 A	MTRS	SEP-1	58
59	ELEV SUMP PUMP ESP-1	MTRS	20 A	1					500 VA	1375...	--	--	--	--	60
			Total Load:		24965 VA		19302 VA		21226 VA						
			Total Amps:		211 A		161 A		179 A						

LP-BA1 LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
RCPTS	2300 VA		2300 VA		
MTRS	39812 VA		39812 VA	**Total Conn. Load:**	65492 VA
MISC	8240 VA		8240 VA	**Total Est. Demand:**	63462 VA
Power	360 VA		360 VA	**Total Conn.:**	182 A
RCPT	14060 VA		12030 VA	**Total Est. Demand:**	176 A

Notes:
*See Demand Factor Table

BRANCH PANEL: ELP-BA1

Location: TOWER A LEVEL B ELEC A018
Main Bus: 225 A
MCB: 150 A
Voltage: 120/208 Wye
AIC Rating: 10 kA

Fed From: T-BA1-E
Wires: 4W + G
Enclosure: NEMA 1
Bus Type: COPPER
Mounting: WALL MOUNTED

Neutral Bus: YES
Ground Bus: YES
Isolated Ground Bus: NO
200% Neutral: NO
Feed Through Lugs: NO

CKT	Circuit Description	Load Classification	Trip	Poles	A		B		C		Poles	Trip	Load Classification	Circuit Description	CKT
1	FIRE SMOKE DAMPERS	MISC	20 A	1	590 VA	500 VA					1	15 A	MISC	ELEV T2 CAR LIGHT	2
3	ELEV PIT GFI RCPT	RCPTS;...	20 A	1			540 VA	500 VA			1	15 A	MISC	ELEV T2 IS INTERCOM	4
5	ELEV SUMP PUMP ESP-2	MTRS	20 A	1					500 VA	500 VA	1	20 A	RCPTS	ELEV T2 CTRL RM GFI RCPT	6
7	FIRE SMOKE DAMPERS	MISC	20 A	1	180 VA	600 VA					1	20 A	MISC	ELEV T2 SEISMIC SENSOR...	8
9	ELEV T1 CTRL RM GFI RCPT	RCPTS	20 A	1			500 VA	180 VA			1	20 A	RCPT	ELEV PIT GFI RCPT	10
11	ELEV T1 CAR LIGHT	MISC	15 A	1					500 VA	500 VA	1	20 A	MTRS	ELEV SUMP PUMP ESP-3	12
13	ELEV T1 SEISMIC SENSOR...	MISC	20 A	1	600 VA	200 VA					1	20 A	MISC	ELEVATOR SMOKE CURTAINS	14
15	ELEV T1 INTERCOM	MISC	15 A	1			500 VA	200 VA			1	20 A	MISC	ELEVATOR SMOKE CURTAINS	16
17	FSD - A-B-8	MISC	20 A	1					50 VA	200 VA	1	20 A	MISC	ELEVATOR SMOKE CURTAINS	18
19	FSD - A-B-7	MISC	20 A	1	50 VA	0 VA					1	20 A	--	SPARE	20
21	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	22
23	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	24
25	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	26
27	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	28
29	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	30
31	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	32
33	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	34
35	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	36
37	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	38
39	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	40
41	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	42
43	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	44
45	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	46
47	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	48
49	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	50
51	SPARE	--	20 A	1			0 VA	0 VA			1	20 A	--	SPARE	52
53	SPARE	--	20 A	1					0 VA	0 VA	1	20 A	--	SPARE	54
55	SPARE	--	20 A	1	0 VA	0 VA					1	20 A	--	SPARE	56
57	SPARE	--	20 A	1			0 VA	0 VA			2	30 A	MISC	SPD	58
59	SPARE	--	20 A	1					0 VA	0 VA	--	--	--	--	60
			Total Load:		2720 VA		2420 VA		2250 VA						
			Total Amps:		23 A		20 A		19 A						

ELP-BA1 LOAD SUMMARY

Load Classification	Connected Load	*Demand Factor	Estimated Demand	Panel Totals	
RCPTS	1180 VA		1180 VA		
MTRS	1000 VA		1000 VA	**Total Conn. Load:**	7390 VA
MISC	4670 VA		4670 VA	**Total Est. Demand:**	7390 VA
RCPT	540 VA		540 VA	**Total Conn.:**	21 A
				Total Est. Demand:	21 A

Notes:
*See Demand Factor Table

Expires 3/31/25
Stamped 5/31/24
Reserved for permit stamp

Olson Kundig
159 South Jackson St, Suite 600
Seattle, Washington 98104 USA
+1 206 624 5670 olsonkundig.com

project
SOMMET BLANC
9500 Marsac Ave (B2 East Parcel)
Park City, Utah 84060

ASPEN GROUP
Aspen Group USA, LLC
PO Box 980022
Park City, Utah 84098

Pool Consultant
Cloward H20
2696 N University Ave, Suite 290
Provo, UT 84604

Landscape Architect
EPG Design
6949 South High Tech Drive, Suite 100
Midvale, Utah 84047

Specifications Writer
Friday Group
88 Mainelli Road
Middebury, VT

Code Consultant
Holmes
600 1st Avenue, Suite 200A
Seattle, WA 98104

Fire Protection Engineer
Jensen Hughes
One Research Drive, Suite 305C
Westborough, MA 01581

Vertical Transportation Consulatant
Lerch Bates
19515 North Creek Parkway, Suite 304
Bothell, WA 98011

Structural Engineer
Magnusson Klemencic Associates
1301 5th Ave, Suite 3200
Seattle, WA 98101

Lighting Designer
O-
1319 SE MLK Blvd, Suite 210
Portland, Oregon 97219

Building Envelope Consultant
RDH
2101 N 34th St
Seattle, WA 98103

Accessibility Consultant
Studio Pacifica
2144 Westlake Ave N, Suite F
Seattle, WA 98109

MEP Engineer
WSP USA
1001 Fourth Ave., Suite 3100
Seattle, WA 98154

principal architect _____
project manager _____
drawn by _____
_____
checked by Checker
job no. _____
date 5/31/2024

revisions:

no.	date	by
2	5/31/2024	IFC 3

IFC Set 3 of 3
5/31/2024

ELECTRICAL SCHEDULES

E6.04AB