

- KEYNOTES:
- MULTIPLE CRITERIA DETECTOR PROGRAMMED FOR ALARM VERIFICATION.
 - FIRE ALARM TERMINAL CABINET WITHIN 2-HR RATED SHUT ACCESSIBLE VIA 2-HR RATED ACCESS PANEL. COORDINATE INSTALLATION AND ACCESS WITH DIVISION 28. TRANSITION FROM 2-HR CC TO FPL CABLE IN SHUT AT THIS POINT.
 - 2-HR CC, SLC AND WAC FROM FCC TO 2-HR RATED SHUT AND STAIRS. ROUTING SHOWN FOR CONCEPTUAL PURPOSES ONLY. MULTIPLE RACEWAYS MAY BE REQUIRED BASED UPON CONDUIT FILL REQUIREMENTS.
 - FULL STATIONS FOR TOTAL BUILDING EVACUATION IN TOWERS AB AND TOWER C.
 - DEDICATED SPEAKER CIRCUIT (2-HR CC) TO STAIR SPEAKERS; TRANSITION TO FPL IN ENT AT FIRST DEVICE.
 - STAIR SPEAKER FOR MANUAL PAGING CONNECTED TO DEDICATED CIRCUIT.

