



159 South Jackson St., Suite 600
Seattle, Washington 98104 USA

Olson Kundig

project: **SOMMET BLANC - ABC**
DEER VALLEY, UTAH

MAGNUSSON
KLEMENCIC
ASSOCIATES

Structural + Civil Engineers
Seattle Chicago
www.mka.com
800.600.3000

checked by _____
job no. 20052
date 05/17/202

revisions

04/08/2024	IFC SET 1 OF 3
11/18/2022	95% CD

IFC SET 2 OF 3

05/17/2024

TOWER A LEVEL 3
REINFORCING
PLAN

S2.A.13.R

8. PROVIDE INTEGRITY BOTTOM BARS PER STUD RAIL SCHEDULE AT ALL COLUMNS. CENTER REINFORCEMENT ON COLUMNS AND PLACE INTEGRITY BARS EACH WAY WITHIN COLUMN VERTICAL REINFORCEMENT. TRIM AND HOOK AT SLAB EDGE AS REQUIRED.

PT TOP REINFORCEMENT SCHEDULE		
MARK	REINFORCING	REMARKS
PT50	(3) #5x5'-2"	HOOK AT END
PT51	(6) #5x6'-8"	HOOK AT END
PT52	(10) #5x9'-2"	HOOK AT END
PT53	(8) #5x6'-8" @ 12"	HOOK AT END
PT54	(6) #5x14'-2"	HOOK AT END
PT55	(8) #5x14'-2" @ 12"	HOOK AT END
PT56	(16) #5x11'-2"	HOOK AT END
PT57	(16) #5x14'-2"	HOOK AT END
PT58	(12) #5x5'-6" @ 12"	HOOK AT END
PT59	(14) #5x11'-2" @ 12"	HOOK AT END
PT60	#5x11'-2" @ 10"	HOOK AT END
PT61	#5x6'-8" @ 10"	HOOK AT END
PT62	#5x9'-0" @ 8"	HOOK AT END
PT63	#5x9'-0" @ 6"	HOOK AT END
PT64	#5x19'-2" @ 12"	HOOK AT END
PT65	#5x14'-2" @ 12"	HOOK AT END

PT BOTTOM REINFORCEMENT SCHEDULE		
MARK	REINFORCING	REMARKS
PB1	#5x10'-0" @ 6"	
PB2	#5x15'-0" @ 12"	
PB7	#5x20'-0" @ 12"	
PB11	#5x15'-0" @ 12"	LAP SPLICE AT DELAY STRIP PER 12/S4.05
PB18	#5x9'-2" @ 12"	HOOK AT END; SEE 20/S5.01

