



1 ECCENTRIC BEAM AT COLUMN




PLAN OF BEAMS

BEAM CONSTRUCTION JOINT




BEAM REINFORCING ELEVATION


11 TYPICAL CONCRETE BEAM



16 TYPICAL CONCRETE UPTURNED BEAM



17 TYP CONC BM AND GIRDER INTERSECTION



18 TYPICAL CONCRETE EDGE BEAM

NOTES:

1. AT CONTRACTOR'S OPTION, WHERE REQUIRED TO RELIEVE BAR CONGESTION, NOT MORE THAN 50 PERCENT OF THE AREA OF THE STRAIGHT BOTTOM BARS MAY BE TERMINATED AS SHOWN UNLESS NOTED OTHERWISE.
2. BEAM SCHEDULES DO NOT INDICATE REQUIREMENTS FOR ARRANGING BARS. THE CONTRACTOR SHALL DETAIL AND PLACE REINFORCING STEEL IN A SINGLE LAYER WHENEVER POSSIBLE. A SECOND LAYER MAY BE USED ONLY WHERE REQUIRED TO PROVIDE PROPER CLEARANCES BETWEEN BARS IN A LAYER AND WHERE REQUIRED IN ORDER TO PROPERLY CLEAR COLUMN VERTICALS AND SIMILAR REINFORCING.
3. EITHER 90 OR 180 DEGREE STANDARD HOOK BARS MAY BE USED FOR LONGITUDINAL BARS.
4. WHERE TOP BARS ARE INDICATED AS CONTINUOUS AND RUN OVER 60 FEET IN LENGTH, BARS MAY BE LAPPED Ld IN THE MIDDLE THIRD OF THE BEAM SPAN UNLESS NOTED OTHERWISE. CONTINUOUS TOP BARS SHALL NOT BE LAPPED IN THE SPAN ADJACENT TO A CANTILEVER, UNLESS NOTED OTHERWISE. WHERE BOTTOM BARS ARE SHOWN AS CONTINUOUS AND RUN IN EXCESS OF 60 FEET, A LAP SPlice MAY BE USED EQUAL TO Lsb AND SHALL BE OUTSIDE THE MIDDLE THIRD OF THE BEAM SPAN. SIDE BAR SPLICES MAY BE MADE WHERE CONVENIENT.
5. LOCATE ALL CONSTRUCTION JOINTS WITHIN THE MIDDLE THIRD OF SPAN. JOINTS SHALL BE OFFSET AT A MINIMUM DISTANCE OF TWO TIMES THE WIDTH OF INTERSECTING BEAMS. SUBMIT LOCATION OF ALL CONSTRUCTION JOINTS TO ENGINEER FOR REVIEW AND ACCEPTANCE BEFORE FORMING.
6. ALL BARS IN SAME LAYER UNLESS NOTED OTHERWISE.


3 TYPICAL CONCRETE BEAM NOTES

CONCRETE BEAM SCHEDULE										
MARK	SIZE (WIDTHxDEPTH)	CAMBER	BOTTOM BARS	TOP BARS			STIRRUPS		REMARKS	
				LEFT	CONTINUOUS	RIGHT	LEFT	RIGHT		
B1	12"x18"		(2) #7	(2) #7	(2) #7	(2) #7	#4 @ 6" [2C]		SEE 1/S4.03	
B2	24"x24"		(3) #8	(7) #8	(7) #8	(7) #8	#5 @ 9" [2C]		SEE 1/S4.03	
B3	24"x24"		(4) #8	(4) #8	(3) #8	(4) #8	#5 @ 9" [2C]		SEE SECTION PER PLAN FOR DEPTH:SEE 1/S4.03	
B5	24"x22" MIN		(3) #8	(9) #9	(9) #9	(9) #9	#5 @ 9" [2C]		SEE SECTION PER PLAN FOR DEPTH:SEE 1/S4.03	
B6	24"x26 1/2"		(3) #8	(5) #9	(4) #9	(5) #9	#5 @ 9" [2C]		SEE 1/S4.03	
B7	24"x24"		(3) #8	(10) #9	(10) #9	(10) #9	#5 @ 9" [3C]		SEE 1/S4.03	
B8	24"x24"		(8) #10	(5) #10	(5) #10	(5) #10	#6 @ 5" [3C]		ADD (2) #4 SIDE BAR EA SIDE: SEE 1/S4.03	
B9	30"x24"		(4) #7	(7) #9	(7) #9	(7) #9	#5 @ 9" [3C]		ADD (3) #4 SIDE BAR EA SIDE:SEE 1/S4.03	
B10	30"x24"		(4) #7	(7) #9	(7) #9	(7) #9	#5 @ 9" [3C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B12	30"x22" MIN		(4) #7	(9) #10	(9) #10	(9) #10	#5 @ 9" [3C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B13	30"x26 1/2"		(5) #7	(10) #10	(10) #10	(10) #10	#5 @ 9" [3C]		ADD (3) #5 SIDE BAR EA SIDE: SEE 1/S4.03	
B16	30"x24"		(4) #7	(9) #8	(9) #8	(9) #8	#4 @ 9" [4C]		ADD (3) #4 SIDE BAR EA SIDE: SEE 1/S4.03	
B17	30"x24"		(4) #7	(9) #8	(9) #8	(9) #8	#4 @ 9" [4C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B21	30"x22" MIN		(4) #7	(10) #10	(10) #10	(10) #10	#6 @ 6" [3C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B22	30"x26 1/2"		(6) #8	(10) #10	(10) #10	(10) #10	#6 @ 6" [3C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B23	30"x26 1/2"		(4) #7	(8) #9	(8) #9	(8) #9	#5 @ 8" [3C]		ADD (2) #4 SIDE BAR EA SIDE - SEE SECTION PER PLAN FOR DEPTH; SEE 1/S4.03	
B26	30"x30"		(3) #7	(4) #7	(4) #7	(4) #7	#5 @ 9" [3C]		SEE 1/S4.03	
B27	30"x30"		(3) #7	(4) #7	(4) #7	(4) #7	#6 @ 6" [2C]		SEE 1/S4.03	
B28	18"x24"		(3) #7	(3) #7	(3) #7	(3) #7	#5 @ 5" [2C]		SEE 1/S4.03	
B29	30"x24"		(4) #7	(6) #8	(6) #8	(6) #8	#5 @ 9" [2C]		SEE 1/S4.03	
B30	30"x24"		(4) #7	(9) #8	(9) #8	(9) #8	#5 @ 10" [2C]		SEE 1/S4.03	
B33	24"x32"		(4) #8	(3) #7	(3) #7	(3) #7	#5 @ 14" [2C]		SEE 1/S4.03	
B34	24"x24"		(4) #8	(4) #8	(4) #8	(4) #8	#5 @ 10" [2C]		SEE 1/S4.03	
B35	24"x24"		(5) #8	(5) #8	(5) #8	(5) #8	#5 @ 10" [2C]		SEE 1/S4.03	
B37	18"x32"		(3) #7	(3) #7	(3) #7	(3) #7	#5 @ 5" [2C]			
B38	24"x32"		(4) #7	(4) #8	(4) #8	(4) #8	#5 @ 14" [2C]			
B39	24"x32"		(4) #8	(4) #8	(4) #8	(4) #8	#5 @ 9" [3C]			
B40	24"x32"		(6) #9	(4) #8	(4) #8	(4) #8	#5 @ 9" [3C]			
B41	34"x30"		(6) #8	(6) #8	(6) #8	(6) #8	#5 @ 9" [3C]			
B42	32"x32"		(4) #9	(4) #9	(4) #9	(4) #9	#4 @ 14" [4C]			
B44	24"x48"		(3) #7	(3) #7	(3) #7	(3) #7	#4 @ 14" [3C]			
B45	24"x48"		(3) #8	(3) #8	(3) #8	(3) #8	#4 @ 14" [3C]			
B46	24"x32"		(3) #8	(3) #8	(3) #8	(3) #8	#4 @ 14" [3C]			
B47	24"x32"		(3) #9	(5) #9	(5) #9	(5) #9	#4 @ 14" [3C]			
B48	24"x50"		(3) #9	(3) #9	(3) #9	(3) #9	#4 @ 14" [3C]			
B49	24"x32"		(3) #9	(3) #9	(3) #9	(3) #9	#4 @ 14" [3C]			
B50	12"x39"		(3) #7	(3) #7	(3) #7	(3) #7	#4 @ 14" [3C]			
B51	18"x32"		(4) #8	(4) #8	(4) #8	(4) #8	#4 @ 10 [4C]			
B52	32"x72"		(14) #11	(4) #10	(3) #10	(3) #10	#5 @ 6" [4C]			
B53	18"x36"		(4) #8	(2) #8	(3) #8	(2) #8	#5 @ 12" [2C]			
B54	24"x32"		(3) #7	(3) #7	(3) #7	(3) #7	#4 @ 14" [3C]			
B56	18"x38"		(3) #9	(3) #9	(3) #9	(3) #9	#4 @ 14" [3C]			
B57	24"x33"		(3) #9	(3) #9	(3) #9	(3) #9	#4 @ 14" [3C]			
B58	30"x36"		(4) #9	(3) #7	(4) #9	(3) #7	(13) #5 @ 6" [4C]	(13) #5 @ 6" [3C]		
B59	24"x62"		(4) #9	(4) #9	(4) #9	(4) #9	#4 @ 12" [4C]			
B61	24"x39"		(6) #10	(6) #8	(6) #8	(6) #8	#4 @ 14" [4C]			
B62	24"x74"		(3) #8	(3) #8	(3) #8	(3) #8	#4 @ 14" [3C]			
B63	24"x72"		(5) #11	(5) #11	(5) #11	(5) #11	#4 @ 14" [3C]			
B64	32"x72"		(8) #11	(8) #11	(8) #11	(8) #11	#5 @ 8" [4C]			
B65	24"x60"		(6) #11	(6) #9	(6) #9	(6) #9	#5 @ 14" [4C]			
B66	24"x74"		(5) #11	(5) #11	(5) #11	(5) #11	#4 @ 14" [3C]			
B67	24"x26"		(3) #8	(3) #8	(3) #8	(3) #8	#4 @ 14" [3C]			
B68	24"x61"		(4) #9	(4) #9	(4) #9	(4) #9	#4 @ 14" [4C]			
B69	30 1/2"x48"		(4) #11	(4) #11	(4) #11	(4) #11	#4 @ 14" [4C]			
B71	40"x42"		(11) #18	(6) #11	(6) #11	(6) #11	#6 @ 4" [4C]			
B72	60"x42"		(14) #11	(8) #9	(8) #9	(8) #9	#5 @ 6" [7C]			
B73	38 1/2"x24"		(3) #7	(3) #8	(3) #8	(3) #8	#5 @ 6" [2C]		SEE DETAIL 18/S5.05	
B74	24"x67"		(5) #9	(5) #9	(5) #9	(5) #9	#5 @ 9" [3C]			
B75	36"x30"		(5) #8	(6) #10	(6) #10	(6) #10	#6 @ 6" [5C]		SEE 1/S4.03	
B76	24"x29" MIN		(4) #9	(4) #8	(4) #8	(4) #8	#5 @ 9" [3C]		25" MINIMUM DEPTH; BOTTOM OF BEAM FLAT AT ELEVATION 8373'-9"; TOP OF BEAM STEPS WITH SLAB	
B77	72"x18"		(6) #6	(2) #6	(2) #6	(2) #6	#5 @ 18" [2]		REINF SIM TO 18/S4.05. SEE PLAN FOR ADDED TOP BAR AT END	
B78	32"x20"		(4) #9	(5) #9	(5) #9	(5) #9	#5 @ 6" [3C]			
B79	12" MIN x 33"		(3) #9	(3) #9	(3) #9	(3) #9	#5 @ 6" [2C]		CLOSED STIRRUPS ARE TO BE CONTINUOUS, NO CAP/TIE PER [2C ALT] ALLOWED. SEE DETAIL 08/S5.02	

NOTES:

1. SEE "TYPICAL CONCRETE BEAM" DETAIL.
2. [] DENOTES TYPE OF REINFORCING CONFIGURATION. SEE "TYPICAL CONCRETE BEAM SECTION AND STIRRUPS" DETAIL FOR STIRRUP TYPE.


13 CONCRETE BEAM SCHEDULE



NOTES:

1. [] DENOTES TYPE OF STIRRUP REINFORCING CONFIGURATION. SEE "CONCRETE BEAM SCHEDULE."

19 TYP CONC BEAM SECTION AND STIRRUPS



Reserved for permit stamp

150 South Jackson St. Suite 600
Seattle, Washington 98104 USA
+1 206 624 9770 olsonkundig.com

Olson Kundig

project
SOMMET BLANC - ABC
DEER VALLEY, UTAH

MAGNUSSON KLEMENCIC
ASSOCIATES

Structural + Civil Engineers

Seattle Chicago
www.mka.com
206 292 1200

principal architect _____

project manager _____

drawn by _____

checked by _____

job no. 20052

date 05/17/2024

revisions:

no. date by
