

DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE DIAGRAMMATIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATION OF EACH RECEPT WITHIN THE ROOM. THE CONTRACTOR SHALL VERIFY THE PLANS USING STANDARD INDUSTRY SYMBOLS. BEFORE ORDERING MATERIALS OR COMMENCEMENT WITH WORK, VERIFY MEASUREMENTS PERTAINING THERETO AND CORRECT ANY DISCREPANCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING DRAWINGS AND CONDITIONS IN THE FIELD. SHALL BE SUBMITTED TO THE CONSTRUCTION MANAGER FOR CONSIDERATION BEFORE PROCEEDING WITH WORK.

F. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THE PERMITS REQUIRED TO INSTALL A COMPLETE ELECTRICAL SYSTEM AS INDICATED ON DRAWINGS AND SPECIFICATIONS.

G. PROVIDE EXIST SIGNS AND CONNECT EXIST SIGNS AND LUMINAIRES NOTED AS EMERGENCY LIGHTS TO THE EXISTING POWER SYSTEM AND TO THE EXISTING PLANS.

H. REFER TO LUMINAIRE SCHEDULE FOR INFORMATION.

I. FUTURE CATALOG NUMBERS ARE SUBJECT TO CHANGE BY THE MANUFACTURER. VERIFY THE CATALOG NUMBERS AND THE MANUFACTURER'S SPECIFICATIONS.

J. VERIFY EQUIPMENT TYPES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.

K. ELECTRICAL CONDUTITS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH OTHER TRADES AND USE CHASES AND CEILING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO ROUGH-IN.

1 MASTER LIGHTING CONTROL OVERRIDE KEYPAD FOR EXTERIOR LIGHTING AND INTERIOR LIGHTING, TO OVERRIDE TIMECLOCK FUNCTION. EXACT LOCATION IS TO BE COORDINATED WITH AND CONFIRMED BY OWNER PRIOR TO INSTALLATION.

