

A. DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE DIAGRAMMATIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATIONS EXCEPT WHERE DIMENSIONS ARE SHOWN. ELECTRICAL WORK IS SHOWN IN PLAIN LINES UNLESS OTHERWISE NOTED.

B. COMMENCEMENT WITH WORK. VERIFY MEASUREMENTS PERTAINING THERETO AND ASSUME RESPONSIBILITY THEREFOR. ANY SUBSTANTIAL DIFFERENCES BETWEEN THE SPECIFIED CONDITIONS AND THOSE SUBMITTED TO THE CONSTRUCTION MANAGER FOR CONSIDERATION BEFORE PROCEEDING WITH WORK.

C. WORK PERFORMED INCLUDES LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO INSTALL ALL ELECTRICAL WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MATERIALS PROVIDED. EXIST SIGNS AND CONNECT EXIST SIGNS AND LUMINAIRES NOTED AS EMERGENCY TO EMERGENCY POWER SOURCE AS INDICATED ON PLANS.

D. REFER TO LUMINAIRE SCHEDULE FOR INFORMATION

E. OBTAIN CATALOG NUMBERS AND SPECIFICATIONS TO CHANGE BY MANUFACTURER. VERIFY FIXTURE CATALOG NUMBERS FOR ACCURACY.

F. VERIFY EQUIPMENT SIZES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY OTHERS.

G. ELECTRICAL CONDUITS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH OTHER TRADES AND USE CHASES AND GELING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO ROUGH-IN.

H. COORDINATE REMOTE DRIVE MOUNTING LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-IN.

I. COORDINATE LUMINAIRE VOLTAGE WITH ARCHITECT AND OTHER PRIOR TO PURCHASE AND INSTALLATION PLANTY FOR ALL UNIT LIGHTING.

1 SUPPLY WIRELESS PICO CONTROL SWITCH IS TO BE PROVIDED AND INSTALLED FOR SHIDE CONTROL. IN THE  
2 LURRY V AND INSTALLED RADIO RAS SYSTEM TO PROVIDE PARTIAL LIGHTING CONTROL. IN THE RESIDENTIAL UNITS MASTER  
3 BEDROOM (DENOTED AS 'BED 1') AND ALL ROOMS WITH MORE THAN THREE (3) LIGHTING CONTROL ZONES ARE TO  
4 BE CONTROLLED BY THE 'BED 1' RADIO RAS SYSTEM. ALL ROOMS WITH THREE (3) LIGHTING CONTROL ZONES OR LESS ARE TO BE  
5 CONTROLLED BY LOCAL DIMMERS.  
6 LIGHT FIXTURE LOCATED IN CLOSETS ARE TO BE CONTROLLED BY CLOSET DOOR JAMB SWITCH.  
7 SUPPLY AND INSTALLED CEILING MOUNTED JUNCTION BOX COMPLETE WITH APPROPRIATE CIRCUIT WIRING FOR INSTALLATION  
8 OF FUTURE GLOUCE LIGHT FIXTURE.  
9 PROVIDE TO ARCHITECT DRAWINGS AND ELEVATIONS FOR EXACT DIMENSION AND MOUNTING LOCATION OF LIGHT FIXTURE  
10 TYPE, LOA, COORDINATE WITH MILLWORK CONTRACTOR PRIOR TO INSTALLATION.



159 South Jackson St, Suite 800  
Seattle, Washington 98104 USA  
+1 206 624 5670 [olsonkundig.com](mailto:olsonkundig.com)

Olson Kundig

project:  
**SOMMET BLANC**  
9300 Marsac Ave (B2 East Parcel)  
Dade City, FL 34608



**Aspen Group USA, LLC**  
PO Box 980022  
Park City, Utah 84098

**Pool Consultant**  
**Cloward H2O**  
2696 N University Ave, Suite 290  
Provo, UT 84604

Landscape Architect  
**EPG Design**  
6949 South High Tech Drive, Suite 100  
Midvale, Utah 84047

Specifications Writer  
**Friday Group**  
88 Mainelli Road  
Middlebury, VT

Code Consultant  
**Holmes**  
600 1st Avenue, Suite 200A  
Seattle, WA 98104

**Fire Protection Engineer**  
**Jensen Hughes**  
One Research Drive, Suite 305C  
Westborough, MA 01581

**Vertical Transportation Consultant**  
**Lerch Bates**  
19515 North Creek Parkway, Suite 304  
Bothell, WA 98011

**Structural Engineer**  
**Magnusson Klemencic Associates**  
1301 5th Ave, Suite 3200  
Seattle, WA 98101

**Lighting Designer**  
O.  
1319 SE MLK Blvd, Suite 210  
Portland, Oregon 97219

**Building Envelope Consultant**  
**RDH**  
2101 N 34th St  
Seattle, WA 98103

**Accessibility Consultant**  
**Studio Pacifica**  
2144 Westlake Ave N, Suite F  
Seattle, WA 98109

**MEP Engineer**  
**WSP USA**  
1001 Fourth Ave., Suite 3100  
Seattle, WA 98154

principal architect \_\_\_\_\_  
project manager \_\_\_\_\_  
drawn by \_\_\_\_\_  
checked by Checker  
job no. \_\_\_\_\_  
date 5/31/2024

revisions:

N	5/2/2025	ASI-011 - WSP
2	5/31/2024	IFC 3

no.      date                          b

IFC Set 3 of 3

5/31/2024

TOWER A/B ELECTRICAL  
LIGHTING PLAN - UNIT A

### E3.4.A