
SHEET NOTES:

- A. DRAWINGS ARE INTENDED TO SHOW GENERAL ARRANGEMENT, DESIGN, AND EXTENT OF WORK AND ARE DIAGRAMMATIC. DRAWINGS ARE NOT INTENDED TO SHOW EXACT LOCATIONS EXCEPT WHERE DIMENSIONS ARE SHOWN. ELECTRICAL WORK IS SHOWN ON PLANS USING STANDARD INDUSTRY SYMBOLS. BEFORE ORDERING MATERIALS OR COMMENCEMENT WITH WORK, VERIFY MEASUREMENTS PERTAINING THERETO AND ASSUME RESPONSIBILITY THEREFOR. ANY SUBSTANTIAL DIFFERENCES BETWEEN DRAWINGS AND CONDITIONS IN THE FIELD SHALL BE SUBMITTED TO THE CONSTRUCTION
- MANAGER FOR CONSIDERATION BEFORE PROCEEDING WITH WORK. B. WORK PERFORMED INCLUDES LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO INSTALL A COMPLETE ELECTRICAL SYSTEM AS INDICATED ON DRAWINGS AND SPECIFICATIONS. PROVIDE EXIT SIGNS AND CONNECT EXIT SIGNS AND LUMINAIRES NOTED AS EMERGENCY TO EMERGENCY POWER SOURCE AS INDICATED ON PLANS.
- D. REFER TO LUMINAIRE SCHEDULE FOR INFORMATION. FIXTURE CATALOG NUMBERS ARE SUBJECT TO CHANGE BY MANUFACTURER. VERIFY FIXTURE CATALOG NUMBERS FOR ACCURACY.
- F. VERIFY EQUIPMENT SIZES AND POWER REQUIREMENTS FOR EQUIPMENT PROVIDED BY ELECTRICAL CONDUITS IN FINISHED SPACES SHALL BE CONCEALED. COORDINATE WITH
- OTHER TRADES AND USE CHASES AND CEILING SPACES. LOCATIONS OF ELECTRICAL JUNCTION BOXES IN FINISHED SPACES SHALL BE APPROVED BY ARCHITECT PRIOR TO
- H. COORDINATE REMOTE DRIVER MOUNTING LOCATIONS WITH ARCHITECT PRIOR TO ROUGH-
- COORDINATE LUMINAIRE VOLTAGE WITH ARCHITECT AND OWNER PRIOR TO PURCHASE AND INSTALLATION TYPICAL FOR ALL UNIT LIGHTING. CONFIRM WITH CLIENT AND OWNER ON UNIT CEILING TYPE FINISH UPGRADES PRIOR TO PURCHASE AND INSTALLATION.

NUMBERED NOTES:

- LIGHT FIXTURE LOCATED IN CLOSETS ARE TO BE CONTROLLED BY CLOSET DOOR JAM SWITCH.
- LUTRON WIRELESS PICO CONTROL SWITCH IS TO BE SUPPLIED AND INSTALLED FOR SHADE CONTROL. SUPPLY AND INSTALL LUTRON RADIO RA2 SYSTEM TO PROVIDE PARTIAL LIGHTING CONTROL IN THE RESIDENTIAL UNITS. MASTER BEDROOM (DENOTED AS 'BED 1') AND ALL ROOMS WITH MORE THAN THREE (3) LIGHTING CONTROL ZONES ARE TO BE CONTROLLED BY THE LUTRON RADIO RA2 SYSTEM. ALL ROOMS WITH THREE (3) LIGHTING CONTROL ZONES OR LESS ARE TO BE
- CONTROLLED BY LOCAL DIMMERS. SUPPLY AND INSTALL CEILING MOUNTED JUNCTION BOX COMPLETE WITH CAPPED LIGHTING CIRCUIT WIRING FOR INSTALLATION OF FUTURE CLOSET LIGHT FIXTURE.
- REFER TO ARCHITECTURAL DRAWINGS AND ELEVATIONS FOR EXACT DIMENSION AND MOUNTING LOCATION OF LIGHT FIXTURE TYPE L04. COORDINATE WITH MILLWORK CONTRACTOR PRIOR TO INSTALLATION.





Reserved for permit stamp

• —

ASPEN GROUP Aspen Group USA, LLC PO Box 980022 Park City, Utah 84098

ool Consultant oward H20 i96 N University Ave, Suite 290 ovo, UT 84604
ndscape Architect PG Design 149 South High Tech Drive, Suite 100 idvale, Utah 84047
pecifications Writer iday Group 3 Mainelli Road iddlebury, VT
ode Consultant olmes 00 1st Avenue, Suite 200A eattle, WA 98104
re Protection Engineer ensen Hughes ne Research Drive, Suite 305C estborough, MA 01581
ertical Transportation Consulatant erch Bates 1515 North Creek Parkway, Suite 304 othell, WA 98011
ructural Engineer agnusson Klemencic Associates 301 5th Ave, Suite 3200 eattle, WA 98101
ghting Designer
119 SE MLK Blvd, Suite 210 ortland, Oregon 97219
uilding Envelope Consultant DH
01 N 34th St eattle, WA 98103
ccessibility Consultant udio Pacifica 44 Westlake Ave N, Suite F eattle, WA 98109

	draw	n by		
	checke	— d bv (Checker	
		no.		
	-			
	(date (5/31/2024	
revi	sions:			
N	05/21/2025		1	
2	5/31/2024	IFC 3		
	date			by

1001 Fourth Ave., Suite 3100 Seattle, WA 98154

principal architect_____

TOWER A/B ELECTRICAL LIGHTING PLAN - UNIT C E3.4.C

IFC Set 3 of 3

5/31/2024