## SECTION 07 4213.16

#### METAL PLATE WALL PANELS

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section includes:
  - 1. Large format metal plate wall panels at back side of chimneys, and at other locations indicated on the Drawings.
  - 2. Aluminum plate, concealed-fastener wall panels.
    - a. Soffits, sills, border, and filler items indicated as integral components of the panel system.
- B. Related Documents and Sections: Examine Contract Documents for requirements that directly affect or are affected by Work of this Section. A list of those Documents and Sections include, but is not limited to the following:
  - 1. Drawings and general provisions of the Contract, including General and Supplementary Conditions and General Requirements.
  - 2. Section 07 4210.11 COMPOSITE FRAMING SUPPORT SYSTEM
  - 3. Section 07 4213 FORMED METAL WALL PANELS
  - 4. Section 07 4243 COMPOSITE METAL WALL PANELS
  - 5. Section 07 4247 HIGH PERFORMANCE GFRC WALL PANELS
  - 6. Section 07 6200 SHEET METAL FLASHING AND TRIM.

#### 1.2 SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. Shop Drawings:
  - 1. Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment assembly, trim, flashings, closures, and accessories; and special details.
  - 2. Accessories: Include details of the flashing, trim, and anchorage, at a scale of not less than 1-1/2 inches per 12 inches (1:10).
- C. Samples for Initial Selection:
  - 1. Provide three samples of finish paint using different roller naps for selection of final finish by the Architect, applied to 12 in. square metal panel material. Show stepped finish process to demonstrate surface preparation, primer applciation, and finish coat(s).
- D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
  - 1. Metal Panels: 12 inches (305 mm) long by actual panel width. Include fasteners, closures, and other metal panel accessories.

- E. Qualification Data: For Installer.
- F. Product Test Reports: For each product, tests performed by a qualified testing agency.
- G. Sample Warranties: For special warranties.
- H. Maintenance Data: For metal panels to include in maintenance manuals.

## 1.3 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
  - 1. Build mockup of typical metal panel chimney backer and typical soffit as directed by the Architect. Refer to Section 01 4339.
  - Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.4 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Retain strippable protective covering on metal panels during installation.

## 1.5 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.

### 1.6 COORDINATION

A. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

#### 1.7 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.

- 1. Failures include, but are not limited to, the following:
  - a. Structural failures including rupturing, cracking, or puncturing.
  - b. Deterioration of metals and other materials beyond normal weathering.
- 2. Warranty Period: Two years from date of Substantial Completion.
- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.
  - 1. Finish Warranty Period: 10 years from date of Substantial Completion.

## PART 2 PRODUCTS

- 2.1 METAL PLATE WALL PANELS
  - A. Metal Plate Wall Panels: Provide factory-formed, metal plate wall panels fabricated from single sheets of metal formed into profile for installation method indicated. Include attachment assembly components, panel stiffeners, and accessories required for weathertight system.
  - B. Panel Depth: As indicated on Drawings.
  - C. Steel Metal-Plate Panels:
    - 1. Product: Custom steel plate system
    - 2. Material: Fabricated with minimum 14 ga. thick or greater as may be required for structural and material performance.
  - D. Attachment Assembly: Clip.
- 2.2 ALUMINUM PLATE PANELS
  - A. Description: Aluminum plate panels.
  - B. Aluminum: To ASTM B209, Alloy 3004 HW32.
  - C. Installation Tolerances
    - 1. Coverage +/- 1/8", Ends +/- 1/6"
  - D. Fabrication:
    - 1. Panel surfaces shall be free of scratches or marks caused during fabrication.
    - 2. Shop fabricate all panel components. Field cutting for penetrations is the only modification allowed. Do not perform cutting without prior approval from manufacturer.
    - 3. Fabricated Panel Tolerances
      - a. Length: Plus 1.6 mm (0.062 inch).
      - b. Width: Plus 1.6 mm (0.062 inch).
      - c. Depth: Plus or minus 0.2 mm (0.008 inch).
      - d. Panel Bow: 0.8 percent maximum of panel length or width.
      - e. Squareness: 5 mm (0.2 inch) maximum.
    - 4. Rainscreen Panels: Provide for positive drainage of condensation and water entering at joints to exterior face of wall in accordance with "Rain Screen Principles". Panels to have drainage holes in bottom of each panel measuring 10 mm (3/8") diameter on 610mm (24") centers, to AAMA 508-07.
  - E. Accessories:

- 1. All fasteners shall be stainless steel.
- 2. Flashing: Aluminum, same finish as for aluminum panel where exposed; secured with concealed fastening method.
- 3. Panel System Subgirts: Provide G90 galvanized steel of gauge and spacing required for panel system structural requirements, as recommended by panel manufacture and in accordance with approved shop drawings. To avoid galvanic reaction, separate dissimilar metals.
- 4. All proprietary extrusions supplied by fabricator.
- 5. No exposed sealant to be used at panel-to-panel connections.
- F. Finish:
  - 1. Fluoropolymer finish, tow coat, as selected by Architect.

#### 2.3 ACCESSORIES

- A. Wall Panel Accessories: Provide components required for a complete assembly including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal wall panels, unless otherwise indicated.
  - 1. Closures: Provide closures fabricated of same metal as metal wall panels.
  - 2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
  - 3. Closure Strips: Closed-cell, expanded, cellular, rubber or crosslinked, polyolefin-foam or closed-cell laminated polyethylene; minimum 1-inch- thick, flexible closure strips; cut or premolded to match metal wall panel profile. Provide closure strips where indicated or necessary to ensure weathertight construction.

#### 2.4 FABRICATION

- A. General: Fabricate and finish metal panels and accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
  - 1. Form panel lines, breaks, and angles to be sharp and true, with surfaces free from warp and buckle.
- B. Metal-Plate Wall Panels: Fabricate panels with panel stiffeners as required to comply with deflection limits. Weld and grind panel corners smooth. Fabricate panels to the following dimensional tolerances:
  - 1. Length and Width: Plus or minus 0.032 inch up to 48 inches; 0.064 inch more than 48 inches.
  - 2. Diagonal: Plus or minus 0.1875 inch.
  - 3. Panel Bow: Not more than 0.2 percent of panel width or length up to 0.1875 inch maximum.
  - 4. Thickness: Plus or minus 0.008 inch.
  - 5. Squareness: 0.1875-inch difference between diagonal measurements.
  - 6. Camber: 0.032 inch.
- C. Sheet Metal Accessories: Fabricate flashing and trim to comply with recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to the design, dimensions, metal, and other characteristics of item indicated.
  - 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to

form hems.

- 2. Sealed Joints: Form non-expansion but movable joints in metal to accommodate elastomeric sealant to comply with SMACNA standards.
- 3. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
- 4. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended by metal wall panel manufacturer.
  - a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal wall panel manufacturer for application but not less than thickness of metal being secured.

### 2.5 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- D. Steel Panel Finish: Provide shop-applied finish as follows:
  - 1. Primer: As recommended by the finish coat manufacturer,
  - Finish Coat: Rust-Oleum Sierra Performance Beyond Acrylic Enamel industrial performance, low VOC, low HAP, very low odor, single component, water-based acrylic urethane.
    a. Color: As selected by the Architect.
  - 3. Application: Rolled on.

# PART 3 EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.
  - 1. Examine subframing to verify that girts, angles, channels, studs, and other structural panel support members and anchorage have been installed within alignment tolerances required by metal wall panel manufacturer.
  - 2. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal wall panel manufacturer.
    - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Examine roughing-in for components and systems penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support

members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

#### 3.3 INSTALLATION

- A. General: Install metal panels in orientation, sizes, and locations indicated. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.
  - 1. Shim or otherwise plumb substrates receiving metal panels.
  - 2. Flash and seal metal panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
  - 3. Install screw fasteners in predrilled holes.
  - 4. Locate and space fastenings in uniform vertical and horizontal alignment.
  - 5. Install flashing and trim as metal panel work proceeds.
  - 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
  - 7. Align bottoms of metal panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
  - 8. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.
- B. Fasteners: Use color-matched stainless steel fasteners for surfaces exposed to the exterior.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.
- D. Attachment Assembly, General: Install attachment assembly required to support metal plate wall panels and to provide a complete weathertight wall system, including subgirts, perimeter extrusions, tracks, drainage channels, panel clips, and anchor channels.
  - 1. Include attachment to supports, panel-to-panel joinery, panel-to-dissimilar-material joinery, and panel-system joint seals.
- E. Installation: Attach metal plate wall panels to supports at locations, spacings, and with fasteners recommended by manufacturer to achieve performance requirements specified.
- F. Clip Installation: Attach panel clips to supports at locations, spacings, and with fasteners recommended by manufacturer. Attach flanges of metal plate wall panels to panel clips with fasteners, as recommended by manufacturer.
  - 1. Seal horizontal and vertical joints between adjacent metal plate wall panels with sealant backing and sealant. Install sealant backing and sealant according to requirements specified in Section 07 9200 JOINT SEALANTS.
- G. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.
  - 1. Install components required for a complete metal panel system including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items. Provide types indicated by metal panel manufacturer; or, if not indicated, provide types recommended in writing by metal panel manufacturer.
- H. Flashing and Trim: Comply with performance requirements, manufacturer's written installation

instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.

- 1. Install exposed flashing and trim that is without buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof performance.
- 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet (3 m) with no joints allowed within 24 inches (605 mm) of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with mastic sealant (concealed within joints).

#### 3.4 ERECTION TOLERANCES

A. Installation Tolerances: Shim and align metal plate wall panel units within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m), non-accumulative, on level, plumb, and location lines as indicated, and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.

## 3.5 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.
- B. After metal panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.
- C. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

# END OF SECTION

# THIS PAGE INTENTIONALLY LEFT BLANK